



TEST REPORT



Doc.NO:F-251

Rev.NO:04

Rev.Date:98/05/08

Customer: QC(ذوب آهن پاسارگارد)

Cyl.NO: Liq Ar

Cylinder arrival date: 02/08/03

Cylinder size: 10 L

Inquiry No: 02L001207

Inquiry date: 02/08/03

Test date: 02/08/10

Report No: 02L001207

Instrument : GC, O2 An, Dewpoint

Lab:Chemical

#	Component	Concentration	Unit	Accuracy	Test method
1	Moisture	2.2	ppm	±10%	
2	Oxygen	2.7	ppm	±10%	
3	Nitrogen	≤5	ppm	±5%	
4	Carbon dioxide	N.D	ppm	±5%	
5	Carbon monoxide	N.D	ppm	±5%	
6	Methane	≤0.5	ppm	±5%	
7	Argon	≥99.999	%	...	

Remark:

A. This test is in accordance with The ISO/IEC 17025 requirements for the competence of testing and calibration laboratories.

NA. This test is not in accordance with The ISO/IEC 17025 requirements for the competence of testing and calibration laboratories./ N.D: Not Detection

This Certificate shall not be copied or reproduced.

This Certificate valid with stamp of farafangas

Uncertainty:

The expanded uncertainty is estimated with attention to coverage factor K=2 normal distribution , providing a level of confidence of approximately 95%

Technical Manager:

Lab Manager:

Date:

Seal:

Farafan Gas Lab:

No,1622,Golestan st. , AbbasAbad Ind . Zone . Km 40 khavaran Rd . , Tehran 3393177669 , Iran

Tel:+98 21 22252500
Email:LAB@FARAFANGAS.COM

Fax:+98 21 2225383
www.farafangas.com

